



IEC 61701:2020
Salt mist corrosion testing of photovoltaic (PV) modules
Confirmation of test results

VDE Renewables File Ref.: ET-20220518-088

Applicant: Jiangsu Runergy New Energy Technology Co., Ltd.
Unit 101, Building 1, 58 Xiangjiang Road, Yancheng Economic and
Technological Development Zones, Yancheng, Jiangsu, China.

Product: Crystalline silicon Photovoltaic (PV)-Modules

Type:	A) HY-DH144P8-XXX	A) HY-DH144P8-XXXb/B/T
	B) HY-DH132P8-XXX	B) HY-DH132P8-XXXb/B/T
	C) HY-DH120P8-XXX	C) HY-DH120P8-XXXb/B/T
	D) HY-DH108P8-XXX	D) HY-DH108P8-XXXb/B/T
	E) HY-DH144N8-XXX	E) HY-DH144N8-XXXb/B/T
	F) HY-DH132N8-XXX	F) HY-DH132N8-XXXb/B/T
	G) HY-DH120N8-XXX	G) HY-DH120N8-XXXb/B/T
	H) HY-DH108N8-XXX	H) HY-DH108N8-XXXb/B/T

XXX in the type replace the power in Watt and can be any number
between:

520 – 550 for A)	470 – 505 for B)	430 – 465 for C)
390 – 420 for D)	540 – 585 for E)	490 – 545 for F)
450 – 495 for G)	405 – 445 for F)	

Manufacturer: Runergy PV Technology (Thailand) Co., Ltd.

Standard: IEC 61701:2020, Salt mist corrosion test

Test conditions

Test method:	6
Testing time:	1344 hrs
Chamber temperature:	40°C
Relative Humidity:	93 %
Mist pH level:	7



Pass criteria

Power degradation:	< 5%
Dry Insulation:	> 40 MΩm ²
Wet insulation:	> 40 MΩm ²
Ground continuity:	< 0.1Ω

Bypass diode functionality: Shall be functional after test

Summary of test results:

Maximum power degradation:	allowed measured	max. 5 % max. 0.39 %
-----------------------------------	---------------------	-------------------------

The measured degradation is below the allowed degradation.

Dry insulation resistance:	required measured	min. 15.5 MΩ >1000 MΩ
-----------------------------------	----------------------	--------------------------

The measured dry insulation resistance is above the limit.

Wet insulation resistance:	required measured	min. 15.5 MΩ >1000 MΩ
-----------------------------------	----------------------	--------------------------

The measured wet insulation resistance is above the limit.

Visual inspection:	No findings
---------------------------	-------------

Ground continuity test:	allowed measured	max. 0.1Ω max. 0.011Ω
--------------------------------	---------------------	--------------------------

Bypass diode functionality test: Still functional after test

The complete test results and the relevant bill of materials are given in Test Report No.: TRPVM- ET-20220518-088-2

VDE Renewables GmbH

Zhiyao Wang
Zhiyao Wang

Dean Wen
Dean Wen

Shanghai, 2022-10-24